Klondike Clean Water Retention Project #11 (January 23 2024 Update)

Project Proposer: Two Rivers Watershed District

Description/Location: The 7,600 acre multi-purpose resource project is located 10 miles east of the City of Lake Bronson, MN and 4 miles north, covering nearly 12 square miles on the Kittson and Roseau County line. It is planned to have gated storage of up to **35,250 acre feet** from a 191.5 square mile upstream drainage area, include 8 miles of diked inlet channel, up to 6 miles of diversion channels, a 17 mile long dike, and an average dike height of 6 feet.

Problem: Large scale overland flooding is a common occurrence from the City of Badger and west to the Kittson & Roseau County line along 18 linear miles of Lateral 1 of State Ditch 95. Undersized channel capacity and the slope of the landscape contributes to out of bank flows and overland flooding on a large scale. In large flood events, water overflows out of the Roseau River and enters the Two Rivers Watershed District via State Ditch #72, exacerbating the problems. Impacts occur to public roads and infrastructure, loss of agricultural crops, and farmsteads. Roads can be closed for several weeks at a time.

Project Benefits: A Project Work Team consisting of representatives of local (County, Watershed District, City, Township), state (DNR, BWSR, MPCA) and federal (NRCS, USFWS, USCOE) agencies as well as local landowners and non-government groups (Nature Conservancy, International Water Institute) was convened. This project team met monthly over the course of several years to

FLOOD DAMAGE REDUCTION

- Store 35,250 acre feet of floodwaters on the land
- *Reduce downstream peak flows and flood duration*
 - - Reduce Two Rivers contribution to Red River peak flows by 15-20%
 - Reduce peak flows on Two Rivers at Lake Bronson State Park by 13%
- *Provide adequate outlet for Lat 1 State Ditch #95*
- Store a portion of Roseau River overflow flooding
- Prevent flooding on over 25 square miles
- Reduce damages to roads, bridges, culverts, farmsteads, and ag lands

Status & Timeline – Pending Funding & Permitting

- Final Plans and Specifications are 90% complete
- Permitting in progress potentially complete by June 2024 (EAW is done, USCOE, WCA, SHPO, 103E ditches, Others)
- Phase 1 16,500 acre ft; fish habitat & water quality 2024-2026
- Phase 2 raise to 27,500 acre ft; fen protection target 2026-2028
- Phase 3 raise to 35,250 acre ft; target 2029-2030

Funding Needs:

- Project Design/Permitting/Right of Way is \$7.2M
- Phase 1 Construction estimate is \$13M \$17.5M
- Phase 2 Construction estimate is \$7M \$9.4M
- Phase 3 Construction estimate is \$5M \$6.7M
- Total Cost = \$32.2M \$42M

Funding secured to date: 2.8 M (LSOHC) 7.2 M (RRWMB) 0.5 State of MN

discuss the project, set goals and investigate alternatives. These meetings followed the process recommended by the <u>Red River</u> <u>Flood Damage Reduction Work Group</u>, which has endorsed the project. This ensures that the project will achieve both flood damage reduction and natural resources enhancement goals and follow proper environmental review procedures.

Natural Resources Enhancements

- Fish Habitat
 - Provide 10-20 cfs flow in Two Rivers during dry periods
 - Prairie Rich Fen
 - $\circ \quad \text{Protect and enhance a large Fen}$
 - o Implement a fen protection plan
- Water Quality Improvements
- Reduce sediment loads to Two Rivers by 62%
- Reduce Phosphorous & Nitrogen loads by 77% & 81%
- Reduce duration and peaks of annual algae blooms at Lake Bronson
- Increase dissolved oxygen levels
- Address water quality impairments on Two Rivers

Μ

THESE ARE ESTIMATES - NUMBERS ARE SUBJECT TO CHANGE AS PROJECT DEVELOPS FURTHER



410 S. 5th St., Ste 112 Hallock, MN 56728

218-843-3333





Project Info @ www.tworiverswd.com/Klondike.html



Preliminary Work: Preferred alternative; Engineer's Report; Final Plans & Specifications; Obtain Right of Way; Obtain Permits; Obtain Funding; Cost \$7.2 Million

Phase 1: Construct dikes to impound 16,500 acre feet; Construct Pilot Channel; Construct 2 outlet structures & spillways; Construct inlet channel; Construct 2 inlet structures; Cost between \$13 Million & \$17.5 Million

Phase 2: Construct/raise dikes to impound 26,750 acre feet; Further work on the diked inlet and road; Cost between \$7 Million & \$9.4 Million

Phase 3: Construct/raise dikes to impound 35,250 acre feet; Construct 4 mile inlet/diversion channel; Cost between \$5 Million & \$6.7 Million